Critical Point and Onset of Deconfinement (CPOD)

23 - 29 August 2010 at Joint Institute for Nuclear Research

Status of NICA Project

I.Meshkov for NICA Project Group

JINR, Dubna



Nuclotron-based Ion Collider fAcility (NICA)

Contents

Introduction: NICA project goals

- **1. Facility scheme and operation scenario**
- 2. NICA Collider
 - 2.1. Layout
 - 2.2. Peak luminosity
 - 2.3. Luminosity preservation
- 3. Status and plan of NICA project development
 - 3.1. Heavy Ion Source KRION-6T
 - 3.2. Heavy Ion Linac 3.3. Booster
 - 3.4. Nuclotron3.5. Collider
 - **3.6. Infrastructure development**
 - **3.7. NICA construction schedule**

Conclusion



Introduction: The NICA Project Goals





Introduction: The NICA Project Goals

The goal of the project is

construction at JINR of a new accelerator facility

that provides

1a) Heavy ion colliding beams ¹⁹⁷Au⁷⁹⁺ x ¹⁹⁷Au⁷⁹⁺ at

1b) Light-Heavy ion colliding beams of the same energy range and luminosity

2) Polarized beams of protons and deuterons in collider mode:

$$\begin{array}{l} p\uparrow p\uparrow \sqrt{s_{pp}} = 12 \div 27 \; GeV \; (5 \div 12.6 \; GeV \; kinetic \; energy \;) \\ d\uparrow d\uparrow \sqrt{s_{NN}} = 4 \div 13.8 \; GeV \; (2 \div 5.9 \; GeV/u \; ion \; kinetic \; energy \\ L_{average} \; \geq \; 1E30 \; cm^{-2} \cdot s^{-1} \; (at \; \sqrt{s_{pp}} = 27 \; GeV) \end{array}$$

3) The beams of light ions and polarized protons and deuterons for fixed target experiments:

Li \div Au = 1 \div 4.5 GeV /u ion kinetic energy p, p^ = 5 \div 12.6 GeV kinetic energy d, d^ = 2 \div 5.9 GeV/u ion kinetic energy

4) Applied research on ion beams at kinetic energy from 0.5 GeV/u

up to 12.6 GeV (p) and 4.5 GeV /u (Au)







I.Meshkov, Status of NICA project

CPOD'2010

5 August 27, 2010 Dubna

1. Facility Scheme and Operation Scenario (Contnd)

Heavy Ion Mode: Operation Regime and Parameters





2. NICA Collider 2.1. Layout

Three versions of the NICA Collider Layout



Y

000

I.Meshkov, Status of NICA project

CPOD'2010

Colider 27- 534 (C_{Ring} = 534 m) July 2010

August 27, 2010 Dubna 7

2.1. Layout (Contnd)

Collider 2T- 534

Advantages of such a large circumference:

- 1. Sufficient space for lattice elements and "insertion devices" (RF cavities, inflectors, electron and stochastic coolers, spin rotators, etc.) that makes possible to construct such a multifunctional collider;
- 2. Continuation of existing fixed target experiments and independent construction of new ones (including test lines for MPD and SPD elements).





2.1. Layout (Contnd)





I.Meshkov, Status of NICA project

2.2. Peak Luminosity

The main limitation of the collider luminosity are the beams space charge effects, which can be described by the following:

1. The Laslett tune shift:
$$\Delta Q = \frac{Z^2}{A} \cdot \frac{r_p N_i}{\beta^2 \gamma^3 4 \pi \varepsilon_{\sigma}} \cdot k_{bunch}, \quad k_{bunch} = \frac{C_{Ring}}{\sqrt{2\pi} \cdot \sigma_s}.$$

2. The beam-beam parameter: $\xi = \frac{Z^2}{A} \cdot \frac{r_p N_b (1 + \beta^2)}{4\pi \beta^2 \gamma \varepsilon}$

More essential is the first one. If $\Delta Q = Const$ with energy then luminosity is scaled with energy as $L \propto \beta^5 \gamma^6 \varepsilon_{geom} = \beta^4 \gamma^5 \varepsilon_{norm}$:

$$L = 8\pi^{2}\beta^{5}\gamma^{6}\Delta Q^{2}\frac{A^{2}}{Z^{4}}\cdot\frac{\varepsilon_{geom}}{r_{p}^{2}\beta^{*}}\cdot\left(\frac{\sigma_{s}}{C_{Ring}}\right)^{2}\cdot\frac{cn_{bunch}}{C_{Ring}} , \text{ where } \sigma_{s} \text{ is the bunch length,}$$

The ratio $C_{Ring}/n_{bunch} = I_{interbunch} = Const$ because it is limited by design of the collider lattice (a necessity to avoid "parasitic" bunch-bunch collisions in straight section). Thus

$$L(E) \propto (\sigma_{\rm s} / C_{\rm Ring})^2 / \beta^*$$



2.2. Peak Luminosity (Contnd)

The reduction of peak luminosity with collider circumference enlargement can be compensated by a proper choice of the beam and lattice parameters:

C _{Ring} , m	251 534			
σ _s , m	0.3	0.6		
β*, m	0.5	0.35		
L ₅₃₄ / L ₂₅₁	0.86			

L(E) \propto ($\sigma_{\rm s}$ / *CRing*) 2 / β^*



I.Meshkov, Status of NICA project

2. NICA Collider (Contnd) 2.2. Peak Luminosity (Contnd) Luminosity scaling with energy

When ⊿Q is fixed the peak luminosity is scaled with energy as the following (two outmost cases):

1. $L_1(E) = Const \cdot \beta^5 \cdot \gamma^6$ if unnormalized ("geometrical") emittance is constant;

10

2. $L_2(E) = Const \beta^4 \chi^5$ if normalized emittance is constant.

Here $\beta(E)$ and $\gamma(E)$ are corent factors.

Luminosity scaling 1E2 for collider 2T- 534 cm $L(4.5 \text{ GeV/u}) = 6E27 \text{ cm}^{-2} \cdot \text{s}^{-1}$ $L (3.5 \text{ GeV/u}) = (1.7 \div 2.1) E27$ 0.01 1.5 2.5 3.5 2 3 4 4.5 $L(1 \text{ GeV/u}) = (0.7 \div 2.1)E25$ E, GeV/u



2.3. Luminosity preservation

Beam life time defined by IBS

If ΔQ is fixed as before then beam life time by IBS is proportional to

$$\tau_{IBS} \propto \frac{A}{Z^2} \cdot \frac{\beta^2 \gamma^2 \varepsilon_{geom} \cdot (\Delta p / p) \cdot \sigma_s}{\Delta Q} \cdot f(\sigma_x, \sigma_y, \sigma_s, lattice functions)$$





I.Meshkov, Status of NICA project

3. Status and plan of NICA elements development 3.1. Heavy Ion Source KRION-6T

(E.D.Donets, E.E.Donets)

Status: Construction of working prototype



Assembled vacuum and cryogenic vessels of the KRION-6T



Automa/ /tool for solenoid spooling





I.Meshkov, Status of NICA project

3.1. Heavy Ion Source KRION-6T (Contnd)

(E.D.Donets, E.E.Donets)





I.Meshkov, Status of NICA project

CPOD'2010

15 August 27, 2010 Dubna

3. Status and plan of NICA elements de

3.2. Heavy lor

HILAC – 1 section of RFQ + 4 sect



2H cavities of "Ural RFQ (prototype)

Status: Design at IHEP (Prot Construction at VNIIE

Государственная корпорация по атомпой энергии "Росатом"	Главн
Федеральное государственное ушитарное предприятие РОССИЙСКИЙ ФЕЛЕРАЛЬНЫЙ	Г.Д. Ц
ЯДЕРНЫЙ ЦЕНТР Всероссийский	Руков
научно-исследовательский институт экспериментальной физики	И.Н. М
ФГУП "РФЯЦ – ВНИИЭФ"	
607188, Нижегородския обл. г.Саров, пр. Мира, д 37 Телетаял 151535 "Миноза" Факе 83130 29494 Е-mail staff@vniief.ru	
25.08.10 No 59499	
на № 010-36/1063 от 02.08.2010	

О возможности изготовления линейного ускорителя Главному инженеру ОИЯИ, г.Дубна Г.Д. Ширкову Руководителю проекта NICA И.Н. Мешкову

Прошу вас для оценки возможности изготовления в РФЯЦ-ВНИИЭФ линейного ускорителя (линака) тяжелых ионов типа RFQ выслать в наш адрес по электронной почте (<u>zavyalov@expd.vniief.ru</u>) комплект рабочей конструкторской документации в формате *.cdw (CAD-naker «Компас») или *.pdf (редактор Adobe Acrobat).

С уважением,

Будников Дмитрий Владимирович 29000 БД 1 24.08.2010

Лиректор ИЯР

Н.В. Завьялов



I.Meshkov, Status of NICA project

CPOD'2010

16 August 27, 2010 Dubna

3.3. Booster

RF system: working design and manufacturing (G.Kurkin and team, Budker INP, by contract)



I.Meshkov, Status of NICA project

3.3. Booster

SC magnetic system: manufacturing of magnet prototypes (H.Khodzhibagiyan and team)



Cross section of the Booster dipole and quadrupole lens

The tool for assembling a curved yoke for the Booster dipoles





I.Meshkov, Status of NICA project

CPOD'2010

Booster dipole yoke at assembling

3.3. Booster

Electron cooler: working design

(A.Shabunov, A.Smirnov, N.Topilin, Yu.Tumanova, S.Yakovenko)





I.Meshkov, Status of NICA project

3.3. Booster

Synchrophasotron dismantling \Rightarrow in progress July 2010





I.Meshkov, Status of NICA project



3.4. Nuclotron

Thorough upgrade since 2007 - after 14 years running

G.Trubnikov, N.Agapov, A.Bazanov, O.Brovko, A.Butenko, A.Govorov, E.Ivanov, V.Karpinsky H.Khodzhibagiyan, V.Mikhailov, V.Monchinsky, A,Sidorin, V.Slepnev, A.Smirnov, V.Volkov



I.Meshkov, Status of NICA project

3.4. Nuclotron

(Contnd)

Parameter	Project	Status (March 2010)
Max. magn. field, T	2.05	1.8
Magn. rigidity, T⋅m	45	39.5
Cycle duration, s	2.0	5.0
B-field ramp, T/s	2.0	1.0
Accelerated particles	p–U, p↑, d↑	p-Xe, d↑
Max. energy, GeV/u	12.6(p), 5.87(d) 4.5(¹⁹⁷ Au ⁷⁹⁺)	5.1(d), 1.0(¹²⁴ Xe ⁴²⁺)
Intensity, ions/cycle	1E11(p,d), 1E9 (A > 100)	3E10 (p,d), 1E10 (d↑) 1E6 (Xe ²⁴⁺)



3.4. Nuclotron (Contnd)

Conceptual scheme of the accelerator complex development



Polarized $p\uparrow$ and $d\uparrow$ beams and protons for p x Au collisions are planned to be accelerated with existing Linac LU-20.



3.4. Nuclotron (Contnd)

Injector (LU-20) modernization

- Upgrade of the power supply system for injection channel;
- Upgrade of vacuum system for fore-injector.



September 2009





I.Meshkov, Status of NICA project

CPOD'2010

24 August 27, 2010 Dubna

3.4. Nuclotron (Contnd)

Upgrade of Nuclotron vacuum system

Upgrade of Nuclotron beam diagnostics system



Elliptical pick-up station



Assembled pick-up station

 Beam slow extraction system at maximum energy
Upgrade of the power supplies and energy evacuation system of the SC magnets

Upgrade of Nuclotron RF (acceleration) system

□ Upgrade of the cryogenic supply system (towards NICA)





3.4. Nuclotron (Contnd)

Nuclotron-NICA

To be designed, constructed and commissioned:

- 1. Injection system (to accept Booster beam)
- 2. RF system new version with bunch compression
- **3.Dedicated diagnostics**
- **4.Single turn extraction with fine synchronization**
- 5.Polarized protons acceleration in Nuclotron*)

*) Can be postponed

To be commissioned in 2014



3.4. Nuclotron (Contnd) Nuclotron - NICA Test experiment on stochastic cooling at Nuclotron Collaboration JINR / FZ Jüb



Stochastic cooling system prototype at Nuclotron for HESR/NICA



Vacuum tank with slot-coupler (FZJ)



I.Meshkov, Status of NICA project

2 ÷ 4 GHz (~10 sec)

CPOD'2010

27 August 27, 2010 Dubna

3.5. Collider

SC magnetic system: manufacturing of magnet prototypes (H.Khodzhibagiyan and team)



c) Quadrupole

"Twin" magnets of NICA collider: Max. field - 2T, super-ferric (Nuclotron-like), double aperture



I.Meshkov, Status of NICA project

3.5. Collider (Contnd)

HV Electron cooler: working design

A.Shabunov, A.Smirnov, N.Topilin, Yu.Tumanova, S.Yakovenko – JINR A.Filippov, M.Pashin, L.Fisher – All-Russian Institute for Electrotechnique





I.Meshkov, Status of NICA project

3. Status and plan of NICA elements development (Contnd) 3.5. Collider (Contnd)

Stochastic cooling system: conceptual design, test experiment
G.Trubnikov, N.Shurkhno, V.Seleznev– JINR, T.Katayama – Tokyo univ.,
R.Stassen – FZJ, L.Thorndahl - CERN

RF systems (Bar. Bucket system, bunching and maintaining RF systems): working design and manufacturing
A.Eliseev, JINR
G.Kurkin and team, Budker INP, by contract



3.6. Infrastructure Development







Building 217 (former LPP workshop)

New cryo-magnetic factory Production, assembly, cryo- and vacuum tests for superconducting magnets serial production for NICA and FAIR (SIS-100)

30 x 75 m²



I.Meshkov, Status of NICA project

3.7. NICA construction schedule

	2010	2011	2012	2013	3 2014	2015	2016
ESIS KRION							
LINAC + channel							
Booster + channel							
Nuclotron-M							
Nuclotron-M \rightarrow NICA							
Channel to collider							
Collider							
Diagnostics							
Power supply							
Control systems							
Cryogenics							
MPD							
Infrastructure							
R&D Design Ma	nufactrng	trng Mount.+commis. Commis/opr		opr Op	eration		



3.7. NICA construction schedule (Contnd)

The main tasks for the NICA project In 2010:

- □ Conceptual / working design of the collider,
- Preparation of the project for the state expertise in accordance with regulations of Russian Federation (under preparation in *The State Specialized Project Institute*, Moscow),
- □ Construction of SC magnets prototypes.

In 2011:

- Passing through the state expertise,
- Beginning of construction of the HILAC, KRION (working version), Booster, the Collider elements,
- Stochastic cooling experiment at Nuclotron.



Conclusion

- The NICA design passed the phase of concept formulation and is presently under
- ✓ detailed simulation of accelerator elements parameters,
- ✓ development of working project,
- ✓ manufacturing and construction of prototypes,
- ✓ preparation of the project for state expertise in accordance with regulations of Russian Federation.

The project realization plan foresees a staged construction and commissioning of accelerators forming the facility. The main goal is the facility commissioning in 2015.





Thank you for your attention!

CPOD'2010



5

I.Meshkov, Status of NICA project

35 August 27, 2010 Dubna